


Downtown Wayfinding Program City of Longmont

90% DESIGN INTENT | LON1693 | NOVEMBER 29, 2021



COLORS	PRINT	PAINT ¹	VINYL FILMS
C1 NAVY BLUE	Pantone 540 C ²	MP13702 Beale Street Blues	Transluscent Graphic Films 540 C Pantone match
C2 COPPER	Pantone 163 C	MP00181 Peachy Pink	Transluscent Graphic Films 163 C custom match Pantone
C3 MEDIUM BLUE	Pantone 653 C	MP09460 Blue Collar	Transluscent Graphic Films 653 C custom match Pantone
C5 SILVER	-	MP18133 Grey Steel Metallic	3M 180-220 Light Silver Metallic Graphic Film
C6 WHITE	-	SOA202SP Natural White (Matthews Factory Mix)	1) 3M 7725 Opaque Matte White 3M 3430 Reflective White (Engineer Grade Prismatic)

¹ Matthews Paint (satin finish unless specified otherwise).

² Certain sign faces or letters require retro-reflective graphics & may need to be printed on 3M Engineer Grade Prismatic Reflective Sheeting (3430) to acheive proper color match (see sign type drawings). DOT/MUTCD requirements must be met.

BRAND GRAPHICS

City Graphic Pattern Designer to provide final artwork



Downtown Graphic Pattern Designer to provide final artwork

CONCRETE BASE FORMS



Scott System Urethane Form Liner

#176 Rough Brick

BRICK/MORTAR COLOR MATCH TBD

FONTS

Fonts must be purchased or obtained by sign fabricator.

T1 Interstate Regular

Aa Bb Cc Dd Ee Ff Gg Hh Ii Jj Kk Ll Mm Nn Oo Pp Qq Rr Ss Tt Uu Vv Ww Xx Yy Zz 1234567890

T2 Interstate Bold

Aa Bb Cc Dd Ee Ff Gg Hh li Jj Kk Ll Mm Nn Oo Pp Qq Rr Ss Tt Uu Vv Ww Xx Yy Zz 1234567890

date 11.29.21	contact	project LON1693	phase 90% Design Intent revision 1	NOT FOR CONSTRUCT
Guide 13110 Shaker Square, Suite 101 Cleveland, Ohio 44120 guidestudio.com	pm C. Fromet design K. Fromet	City of Longmont Downtown Wayfinding Program	Color, Materials, Graphics Program Specifications	actual fabrication purp and installation methoo identical to constructio alterations while under user's sole risk and with specifications for detail Copyright © Guide Stu

GRAPHICS



Arrow Designer to provide final artwork


X dimension should remain the same when rotating arrow




UCTION

notes are for the sole purpose of expressing visual design intent and are not intended for urposes. Sign Contractor accepts total responsibility for final material selection, fabrication thods. Electronic files are not cwonstruction documents and cannot be relied upon as iction documents because of changes or errors induced by translation, transmission, or der the control of others. Use of information contained in the electronic files is at the without liability to Design Professional and its consultants. Refer to provided performance etails on designer expectations of Fabricator and fabrication process. Studio, Inc. All rights reserved.

sheet




date 11.29.21		contact	project LON1693	phase 90% Design Intent revision 0	NOT FOR CONSTRUC These drawings and n
Guide	13110 Shaker Square, Suite 101 Cleveland, Ohio 44120 guidestudio.com	pm C. Fromet design K. Fromet	City of Longmont Downtown Wayfinding Program	Sign Family	actual fabrication purp and installation metho identical to construction alterations while under user's sole risk and with specifications for detain Copyright © Guide Stu




- 1. Sign contractor shall be responsible for design and engineering of supports, anchors and miscellaneous steel or metal required for installation.
- 2. The sign contractor's structural engineer shall be licensed in the State of Colorado and certify all connections and support details.
- 3. Isolate dissimilar materials as required.
- 4. Field dimensions shall be taken by the sign contractor prior to preparation of shop drawings and fabrication wherepossible. It is the responsibility of the sign contractor to site verify all sign locations for accuracy, fit, and potential obstacles. Sign contractor shall notify appropriate person(s) of any issues, discrepancies and potential obstacles per the attached Performance Specifications, contract or specified communication process.
- 5. It is the responsibility of the sign contractor to contact appropriate organizations to verify locations of underground utilities.
- 6. Sign contractor must obtain all permits and field inspection approvals necessary to complete work per City requirements. All sign locations need to be located and staked by sign contractor and approved by the City prior to installation.
- 7. Masonry dimensions are approximate; sign contractor to verify and adjust as needed. Final dimensions must appear on shop drawings for review and approval.
- 8. Sign contractor must clean and seal masonry to prevent moisture, discoloration and other defects due to weather and environmental conditions.
- 9. Sign contractor must submit brick, stone, and mortar samples for review and approval.
- 10. Sign contractor shall follow any additional requirements presented in the attached Performance Specifications and Design Intent Documents.

These drawings and notes are for the sole purpose of expressing visual design intent and are not intended for actual fabrication purposes. Sign Contractor accepts total responsibility for final material selection, fabrication and installation methods. Electronic files are not cwonstruction documents and cannot be relied upon as identical to construction documents because of changes or errors induced by translation, transmission, or alterations while under the control of others. Use of information contained in the electronic files is at the user's sole risk and without liability to Design Professional and its consultants. Refer to provided performance specifications and window adding to Design Professional and its Consultants. Refer to p specifications for details on designer expectations of Fabricator and fabrication process. Copyright © Guide Studio, Inc. All rights reserved.









SCALE: 1"=1'

SCALE: 1"=1

date 11.29.21		contact	project LON1693	phase 90% Design Intent revision 0	NOT FOR CONSTRUCTION These drawings and notes are for
Guide	13110 Shaker Square, Suite 101 Cleveland, Ohio 44120 guidestudio.com	pm C. Fromet design K. Fromet	City of Longmont Downtown Wayfinding Program	Downtown Directional Sign Type DWF.1	actual fabrication purposes. Sigr and installation methods.Electro identical to construction docum alterations while under the cont user's sole risk and without liabil specifications for details on desi Copyright © Guide Studio, Inc. A


GENERAL NOTES


- Sign contractor shall be responsible for design and engineering of supports, anchors and miscellaneous steel or metal required for installation.
- 2. The sign contractor's structural engineer shall be licensed in the State of Colorado and certify all connections and support details.
- 3. Isolate dissimilar materials as required.
- 4. Field dimensions shall be taken by the sign contractor prior to preparation of shop drawings and fabrication wherepossible. It is the responsibility of the sign contractor to site verify all sign locations for accuracy, fit, and potential obstacles. Sign contractor shall notify appropriate person(s) of any issues, discrepancies and potential obstacles per the attached Performance Specifications, contract or specified communication process.
- It is the responsibility of the sign contractor to contact appropriate organizations to verify locations of underground utilities.
- Sign contractor must obtain all permits and field inspection approvals necessary to complete work per City requirements. All sign locations need to be located and staked by sign contractor and approved by the City prior to installation.
- Masonry dimensions are approximate; sign contractor to verify and adjust as needed. Final dimensions must appear on shop drawings for review and approval.
- Sign contractor must clean and seal masonry to prevent moisture, discoloration and other defects due to weather and environmental conditions.
- 9. Sign contractor must submit brick, stone, and mortar samples for review and approval.
- 10. Sign contractor shall follow any additional requirements presented in the attached Performance Specifications and Design Intent Documents.

Die cut out of vinyl decal

d notes are for the sole purpose of expressing visual design intent and are not intended for purposes. Sign Contractor accepts total responsibility for final material selection, fabrication ethods. Electronic files are not cwonstruction documents and cannot be relied upon as action documents because of changes or errors induced by translation, transmission, or nder the control of others. Use of information contained in the electronic files is at the without liability to Design Professional and its consultants. Refer to provided performance letails on designer expectations of Fabricator and fabrication process. 2 Studio, Inc. All rights reserved.







COLOR BREAKDOWN	LAYOU
SCALE: 1"=1'	

SCALE: 1"=1'

date 11.29.21	contact	project LON1693	phase 90% Design Intent revision 0	NOT FOR CONSTRUC
Guide 13110 Shaker Square, Suite 101 Cleveland, Ohio 44120 guidestudio.com	pm C. Fromet design K. Fromet	City of Longmont Downtown Wayfinding Program	Downtown Directional Sign Type DWF.2	actual fabrication purp and installation metho identical to constructio alterations while under user's sole risk and wit specifications for detai Copyright © Guide Stu

GENERAL NOTES


- 1. Sign contractor shall be responsible for design and engineering of supports, anchors and miscellaneous steel or metal required for installation.
- 2. The sign contractor's structural engineer shall be licensed in the State of Colorado and certify all connections and support details.
- 3. Isolate dissimilar materials as required.
- 4. Field dimensions shall be taken by the sign contractor prior to preparation of shop drawings and fabrication wherepossible. It is the responsibility of the sign contractor to site verify all sign locations for accuracy, fit, and potential obstacles. Sign contractor shall notify appropriate person(s) of any issues, discrepancies and potential obstacles per the attached Performance Specifications, contract or specified communication process.
- 5. It is the responsibility of the sign contractor to contact appropriate organizations to verify locations of underground utilities.
- 6. Sign contractor must obtain all permits and field inspection approvals necessary to complete work per City requirements. All sign locations need to be located and staked by sign contractor and approved by the City prior to installation.
- 7. Masonry dimensions are approximate; sign contractor to verify and adjust as needed. Final dimensions must appear on shop drawings for review and approval.
- 8. Sign contractor must clean and seal masonry to prevent moisture, discoloration and other defects due to weather and environmental conditions.
- 9. Sign contractor must submit brick, stone, and mortar samples for review and approval.
- 10. Sign contractor shall follow any additional requirements presented in the attached Performance Specifications and Design Intent Documents.

sheet

5

RUCTION

nd notes are for the sole purpose of expressing visual design intent and are not intended for purposes. Sign Contractor accepts total responsibility for final material selection, fabrication ethods. Electronic files are not cwonstruction documents and cannot be relied upon as uction documents because of changes or errors induced by translation, transmission, or nder the control of others. Use of information contained in the electronic files is at the without liability to Design Professional and its consultants. Refer to provided performance details on designer expectations of Fabricator and fabrication process. e Studio, Inc. All rights reserved.



These drawings and notes are for the sole purpose of expressing visual design intent and are not intended for actual fabrication purposes. Sign Contractor accepts total responsibility for final material selection, fabrication and installation methods. Electronic files are not cwonstruction documents and cannot be relied upon as identical to construction documents because of changes or errors induced by translation, transmission, or alterations while under the control of others. Use of information contained in the electronic files is at the user's sole risk and without liability to Design Professional and its consultants. Refer to provided performance specifications for details on designer expectations of Fabricator and fabrication process Specifications for details on designer expectations of Fabricator and fabrication process Copyright © Guide Studio, Inc. All rights reserved.


Stainless steel straps through c-channel

GENERAL NOTES

- 1. Sign contractor shall be responsible for design and engineering of supports, anchors and miscellaneous steel or metal required for installation.
- 2. The sign contractor's structural engineer shall be licensed in the State of Colorado and certify all connections and support details.
- 3. Isolate dissimilar materials as required.
- 4. Field dimensions shall be taken by the sign contractor prior to preparation of shop drawings and fabrication wherepossible. It is the responsibility of the sign contractor to site verify all sign locations for accuracy, fit, and potential obstacles. Sign contractor shall notify appropriate person(s) of any issues, discrepancies and potential obstacles per the attached Performance Specifications, contract or specified communication process.
- 5. It is the responsibility of the sign contractor to contact appropriate organizations to verify locations of underground utilities.
- 6. Sign contractor must obtain all permits and field inspection approvals necessary to complete work per City requirements. All sign locations need to be located and staked by sign contractor and approved by the City prior to installation.
- 7. Masonry dimensions are approximate; sign contractor to verify and adjust as needed. Final dimensions must appear on shop drawings for review and approval.
- 8. Sign contractor must clean and seal masonry to prevent moisture, discoloration and other defects due to weather and environmental conditions.
- 9. Sign contractor must submit brick, stone, and mortar samples for review and approval.
- 10. Sign contractor shall follow any additional requirements presented in the attached Performance Specifications and Design Intent Documents.



sheet




date 11.29.21	contact	project LON1693	phase 90% Design Intent revision 0	NOT FOR O These drav
Guide 13110 Shaker Square, Suite 101 Cleveland, Ohio 44120 guidestudio.com	pm C. Fromet design K. Fromet	City of Longmont Downtown Wayfinding Program	Downtown Trailblazer Sign Type DWF.3/DWF.4	actual fabri and installa identical to alterations user's sole specificatio Copyright

- 1. Sign contractor shall be responsible for design and engineering of supports, anchors and miscellaneous steel or metal required for installation.
- 2. The sign contractor's structural engineer shall be licensed in the State of Colorado and certify all connections and support details.
- 3. Isolate dissimilar materials as required.
- 4. Field dimensions shall be taken by the sign contractor prior to preparation of shop drawings and fabrication wherepossible. It is the responsibility of the sign contractor to site verify all sign locations for accuracy, fit, and potential obstacles. Sign contractor shall notify appropriate person(s) of any issues, discrepancies and potential obstacles per the attached Performance Specifications, contract or specified communication process.
- It is the responsibility of the sign contractor to contact appropriate organizations to verify locations of underground utilities.
- Sign contractor must obtain all permits and field inspection approvals necessary to complete work per City requirements. All sign locations need to be located and staked by sign contractor and approved by the City prior to installation.
- Masonry dimensions are approximate; sign contractor to verify and adjust as needed. Final dimensions must appear on shop drawings for review and approval.
- Sign contractor must clean and seal masonry to prevent moisture, discoloration and other defects due to weather and environmental conditions.
- 9. Sign contractor must submit brick, stone, and mortar samples for review and approval.
- 10. Sign contractor shall follow any additional requirements presented in the attached Performance Specifications and Design Intent Documents.

NOT FOR CONSTRUCTION

drawings and notes are for the sole purpose of expressing visual design intent and are not intended for fabrication purposes. Sign Contractor accepts total responsibility for final material selection, fabrication stallation methods. Electronic files are not cwonstruction documents and cannot be relied upon as al to construction documents because of changes or errors induced by translation, transmission, or ions while under the control of others. Use of information contained in the electronic files is at the sole risk and without liability to Design Professional and its consultants. Refer to provided performance cations for details on designer expectations of Fabricator and fabrication process. ght © Guide Studio, Inc. All rights reserved.





- 1. Sign contractor shall be responsible for design and engineering of supports, anchors and miscellaneous steel or metal required for installation.
- 2. The sign contractor's structural engineer shall be licensed in the State of Colorado and certify all connections and support details.
- 3. Isolate dissimilar materials as required.
- 4. Field dimensions shall be taken by the sign contractor prior to preparation of shop drawings and fabrication wherepossible. It is the responsibility of the sign contractor to site verify all sign locations for accuracy, fit, and potential obstacles. Sign contractor shall notify appropriate person(s) of any issues, discrepancies and potential obstacles per the attached Performance Specifications, contract or specified communication process.
- 5. It is the responsibility of the sign contractor to contact appropriate organizations to verify locations of underground utilities.
- 6. Sign contractor must obtain all permits and field inspection approvals necessary to complete work per City requirements. All sign locations need to be located and staked by sign contractor and approved by the City prior to installation.
- 7. Masonry dimensions are approximate; sign contractor to verify and adjust as needed. Final dimensions must appear on shop drawings for review and approval.
- 8. Sign contractor must clean and seal masonry to prevent moisture, discoloration and other defects due to weather and environmental conditions.
- 9. Sign contractor must submit brick, stone, and mortar samples for review and approval.
- 10. Sign contractor shall follow any additional requirements presented in the attached Performance Specifications and Design Intent Documents.

These drawings and notes are for the sole purpose of expressing visual design intent and are not intended for actual fabrication purposes. Sign Contractor accepts total responsibility for final material selection, fabrication and installation methods. Electronic files are not cwonstruction documents and cannot be relied upon as identical to construction documents because of changes or errors induced by translation, transmission, or alterations while under the control of others. Use of information contained in the electronic files is at the user's sole risk and without liability to Design Professional and its consultants. Refer to provided performance specifications for details on designer expectations of Fabricator and fabrication process. Copyright © Guide Studio, Inc. All rights reserved.







- L					
	date 11.29.21	contact	project LON1693	phase 90% Design Intent revision 0	NOT FOR CONSTRUCT
	Guide 13110 Shaker Square, Suite 101 Cleveland, Ohio 44120 guidestudio.com	pm C. Fromet design K. Fromet	City of Longmont Downtown Wayfinding Program	Parking Lot Identification Sign Type PID.1	actual fabrication purp and installation methor identical to construct alterations while unde user's sole risk and wi specifications for deta Copyright © Guide St


- 1. Sign contractor shall be responsible for design and engineering of supports, anchors and miscellaneous steel or metal required for installation.
- 2. The sign contractor's structural engineer shall be licensed in the State of Colorado and certify all connections and support details.
- 3. Isolate dissimilar materials as required.
- 4. Field dimensions shall be taken by the sign contractor prior to preparation of shop drawings and fabrication wherepossible. It is the responsibility of the sign contractor to site verify all sign locations for accuracy, fit, and potential obstacles. Sign contractor shall notify appropriate person(s) of any issues, discrepancies and potential obstacles per the attached Performance Specifications, contract or specified communication process.
- It is the responsibility of the sign contractor to contact appropriate organizations to verify locations of underground utilities.
- Sign contractor must obtain all permits and field inspection approvals necessary to complete work per City requirements. All sign locations need to be located and staked by sign contractor and approved by the City prior to installation.
- Masonry dimensions are approximate; sign contractor to verify and adjust as needed. Final dimensions must appear on shop drawings for review and approval.
- Sign contractor must clean and seal masonry to prevent moisture, discoloration and other defects due to weather and environmental conditions.
- 9. Sign contractor must submit brick, stone, and mortar samples for review and approval.
- 10. Sign contractor shall follow any additional requirements presented in the attached Performance Specifications and Design Intent Documents.

sheet

9

RUCTION

Ind notes are for the sole purpose of expressing visual design intent and are not intended for purposes. Sign Contractor accepts total responsibility for final material selection, fabrication tethods.Electronic files are not cwonstruction documents and cannot be relied upon as ruction documents because of changes or errors induced by translation, transmission, or under the control of others. Use of information contained in the electronic files is at the id without liability to Design Professional and its consultants. Refer to provided performance details on designer expectations of Fabricator and fabrication process. Is Studio, Inc. All rights reserved.





- 1. Sign contractor shall be responsible for design and engineering of supports, anchors and miscellaneous steel or metal required for installation.
- 2. The sign contractor's structural engineer shall be licensed in the State of Colorado and certify all connections and support details.
- 3. Isolate dissimilar materials as required.
- 4. Field dimensions shall be taken by the sign contractor prior to preparation of shop drawings and fabrication wherepossible. It is the responsibility of the sign contractor to site verify all sign locations for accuracy, fit, and potential obstacles. Sign contractor shall notify appropriate person(s) of any issues, discrepancies and potential obstacles per the attached Performance Specifications, contract or specified communication process.
- 5. It is the responsibility of the sign contractor to contact appropriate organizations to verify locations of underground utilities.
- 6. Sign contractor must obtain all permits and field inspection approvals necessary to complete work per City requirements. All sign locations need to be located and staked by sign contractor and approved by the City prior to installation.
- 7. Masonry dimensions are approximate; sign contractor to verify and adjust as needed. Final dimensions must appear on shop drawings for review and approval.
- 8. Sign contractor must clean and seal masonry to prevent moisture, discoloration and other defects due to weather and environmental conditions.
- 9. Sign contractor must submit brick, stone, and mortar samples for review and approval.
- 10. Sign contractor shall follow any additional requirements presented in the attached Performance Specifications and Design Intent Documents.

SECURITY DETAIL NOT TO SCALE

actual fabrication purposes. Sign Contractor accepts total responsibility for final material selection, fabrication and installation methods.Electronic files are not cwonstruction documents and cannot be relied upon as identical to construction documents because of changes or errors induced by translation, transmission, or alterations while under the control of others. Use of information contained in the electronic files is at the user's sole risk and without liability to Design Professional and its consultants. Refer to provided performance specifications for details on designer expectations of Fabricator and fabrication process. Copyright © Guide Studio, Inc. All rights reserved.








date 11.29.21		contact	project LON1693	phase 90% Design Intent revision 0	NOT FOR CONSTRUC These drawings and no actual fabrication purp
Cuida	13110 Shaker Square, Suite 101 Cleveland, Ohio 44120	pm C. Fromet	City of Longmont	Pedestrian Kiosk - Small	and installation metho identical to construction alterations while under
Guide	guidestudio.com	design K. Fromet	Downtown Wayfinding Program	Sign Type PK2	user's sole risk and wit specifications for detai Copyright © Guide Stu

- 1. Sign contractor shall be responsible for design and engineering of supports, anchors and miscellaneous steel or metal required for installation.
- 2. The sign contractor's structural engineer shall be licensed in the State of Colorado and certify all connections and support details.
- 3. Isolate dissimilar materials as required.
- 4. Field dimensions shall be taken by the sign contractor prior to preparation of shop drawings and fabrication wherepossible. It is the responsibility of the sign contractor to site verify all sign locations for accuracy, fit, and potential obstacles. Sign contractor shall notify appropriate person(s) of any issues, discrepancies and potential obstacles per the attached Performance Specifications, contract or specified communication process.
- It is the responsibility of the sign contractor to contact appropriate organizations to verify locations of underground utilities.
- 6. Sign contractor must obtain all permits and field inspection approvals necessary to complete work per City requirements. All sign locations need to be located and staked by sign contractor and approved by the City prior to installation.
- Masonry dimensions are approximate; sign contractor to verify and adjust as needed. Final dimensions must appear on shop drawings for review and approval.
- Sign contractor must clean and seal masonry to prevent moisture, discoloration and other defects due to weather and environmental conditions.
- 9. Sign contractor must submit brick, stone, and mortar samples for review and approval.
- 10. Sign contractor shall follow any additional requirements presented in the attached Performance Specifications and Design Intent Documents.





"Pin in TORX" tamper resistant screws (stainless steel)

sheet

RUCTION

In dinotes are for the sole purpose of expressing visual design intent and are not intended for purposes. Sign Contractor accepts total responsibility for final material selection, fabrication ethods.Electronic files are not cwonstruction documents and cannot be relied upon as uction documents because of changes or errors induced by translation, transmission, or inder the control of others. Use of information contained in the electronic files is at the d without liability to Design Professional and its consultants. Refer to provided performance details on designer expectations of Fabricator and fabrication process. e Studio, Inc. All rights reserved.